#### Dear Barathi

Many thanks for the nomination and support, we confirm attendance

Best regards
Manoj Kewalramani
Executive Director – South East Asia
Agrimin Control International Pte. Ltd.
#42-01, Suntec Tower Three
8,Temasek Boulevard
Singapore 038988

DID : + 65 6829 2161 HP : + 65 9129 2919

Email: Manoj.Kewalramani@agrimincontrol.com

Web: www.agrimincontrol.com



From: Barathi <barathi@valencyinternational.com>

Sent: Thursday, 15 October 2020 1:18 PM

To: Manoj Kewalramani < manoj.kewalramani@agrimincontrol.com >

Cc: Vishnu <vishnu@valencyinternational.com>; AGRIMIN INDO <operations-

indo@agrimincontrol.com>; Siddharth Amin <siddharth.amin@agrimincontrol.com>; Priyanka <priyanka@valencyinternational.com>; Aarti Poddar <Aarti.Poddar@agrimincontrol.com>; Sandar <sandar@valencyinternational.com>

Subject: RE: Bagging - Stuffing Inspection nomination - Portklang (New Nomination)

LNLUPKL8072488 (10x20') & LNLUPKL8073006 (15x20')

Importance: High

Dear Mr. Manoj,

Product: Granular urea Contact Details: Mr. Nazari

Location:

Berjaya Baja Servis Sdn Bhd Located at PT4231 (Lot 26725), Lingkaran Sultan Hishamuddin, Kawasan Perusahaan Selat Klang Utara, 42000 Pelabuhan Klang (nearby Hainan Village), Selangor Darul Ehsan, Malaysia. **Booking Number:** 

LNLUPKL8072488 (10x20') LNLUPKL8073006 (15x20')

POL: Port Klang, Malaysia POD: Yangon, Myanmar

Marking & Quantity:

Green Gold Flower - 10 FCL + 15 FCL

# **Basic requirement for POL Inspection as follows:**

#### Container:

Checking the cleanliness of containers & its sound condition before stuffing.

Share with us the stages of picture starting from empty containers till the container sealed.

Rejection of containers that are damaged and not seaworthy.

Verification of quantity against weigh bridge slips .

Actual counting of Bags before sealing the containers.

Rejection of cargo if it deviates from the specification.

Reading of Container wise Gross Weight & Net weight.

Inspection seal is mandatory and picture to be taken to show container number & Inspection seal number & Shipping line seal number.

# Bagging:

Ensure no visible dirt, severely discoloured urea and lumps are removed.

Ensure cargo packed in bags is free flowing & cargo is as pure as possible but to maintain same packing rate as trial

Check weighing machine calibration before allowing for bagging. Net weight should be **50kgs** (no minus tolerance)

Verification of Bag marking and Bag Drop tests to ensure they are sound.

Rejection of Torn or Partial stitching bags. Bags should be double stitched.

1% of empty extra bags are required. Once stuffing complete, pls advise container number where empty extra bags kept along with total number of empty extra bags in each container Foreign particles limited to 1% max.

## **Quality:**

The below analysis to be performed on the one composite sample taken during stuffing.

### **Specifications:**

Analysis on one composite sample drawn and the details as following:

**Granular UREA** 

Moisture:1.0% maximumNitrogen:46% minimumBiuret:1.0% maximum

Physical condition : Granular, free flowing non-caking, White in

colour.

PARTICLE SIZE : NOT LESS THAN 90PCT OF THE MATERIAL SHALL PASS THROUGH A SIEVE OF APERTURE SIZE OF 4.00MM AND NOT MORE THAN 5 PERCENT OF THE MATERIAL SHALL PASSES THROUGH A SIEVE OF APERTURE SIZE OF 2MM.

•••••	•••••	 •••••	•••••

### Note:

- 1. Pls stop bagging or loading of cargo immediately and contact us in the event that there is deviation from any of the above requirements.
- 2. Inspection status to be update to us on daily basis and testing report to receive prior to the container loading into the vessel.
- 3. Issuance of final certificates: Certificate of Quality, Quantity and Analysis in 1 original and 2 copies.